

TOWN OF WELLINGTON PLANNING COMMISSION June 2, 2025 6:30 PM

Leeper Center, 3800 Wilson Avenue, Wellington CO

REGULAR MEETING

Individuals wishing to make public comments must attend the meeting in person or submit comments by sending an email to checkettai@wellingtoncolorado.gov The email must be received by 3:00 p.m. Friday, May 2, 2025. After that time, written public comments cannot be accepted. The comments will be provided to the Commissioners at the meeting. Emailed comments will not be read during the meeting.

The Zoom information below is for online viewing and listening only.

Please click the link below to join the webinar: https://us06web.zoom.us/j/83942324094

Webinar ID: 839 4232 4094

Or One tap mobile: US: +17207072699,,87576162114# or +12532158782,,87576162114# Or Telephone: US: +1 720 707 2699 or +1 253 215 8782 or +1 346 248 7799

- 1. CALL TO ORDER
- 2. ROLL CALL
- 3. ADDITIONS TO OR DELETIONS FROM THE AGENDA
- PUBLIC FORUM
- CONSIDERATION OF MINUTES
 - A. Regular Meeting Minutes of May 5, 2025
- 6. NEW BUSINESS
 - A. Public Hearing considering a Final Plat for Wellington Business Center, Amendment No. 1
 - B. Review of Amended Site Development Plans for Lots 1 and 2, Block 2, Bonfire Subdivision 2nd Filing
- 7. COMMUNICATIONS
- 8. ADJOURNMENT

The Town of Wellington will make reasonable accommodations for access to Town services, programs, and activities and special communication arrangements Individuals needing special accommodation may request assistance by contacting at Town Hall or at 970-568-3381 at least 24 hours in advance.



Planning Commission Meeting

Date: June 2, 2025

Submitted By: Aidan Checkett, Planner 1

Subject: Regular Meeting Minutes of May 5, 2025

EXECUTIVE SUMMARY

N/A

BACKGROUND / DISCUSSION

N/A

STAFF RECOMMENDATION

Move to approve the regular meeting minutes of the May 5, 2025 Planning Commission meeting, as presented.

ATTACHMENTS

1. Meeting Minutes of May 5, 2025



TOWN OF WELLINGTON PLANNING COMMISSION May 5, 2025

MINUTES REGULAR MEETING – 6:30 PM

1. CALL REGULAR MEETING TO ORDER – 6:31 p.m.

The Planning Commission for the Town of Wellington, Colorado, met on May 5, 2025, at the Wilson Leeper Center, 3800 Wilson Avenue, Wellington, Colorado at 6:31 p.m.

2. ROLL CALL

Commissioners Present: Eric Sartor, Chairperson

Sherman Stringer
Bert McCaffrey
Lisa Chollet
Linda Knaack
Tim Whitehouse
Stephen Carman
(arrived 6:33 PM)

Absent:

Town Staff Present: Brittan

Cody Bird, Planning Director Brittany Lenoir, Planner III Aidan Checkett, Planner I

Patti Garcia, Town Administrator

3. ADDITIONS TO OR DELETIONS FROM THE AGENDA

None

4. PUBLIC FORUM

There was no public comment.

5. CONSIDERATION OF MINUTES

Commissioner Carman moved to approve the regular meeting minutes of April 7, 2025. Commissioner Whitehouse seconded.

Yeas – Chollet, Stringer, Sartor, McCaffrey, Knaack, Whitehouse, Carman Nays-

Motion carried.

6. NEW BUSINESS

A. Consideration of a Preliminary Plat for Sage Farms Filing 1 located East of State Highway 1 and South of G.W. Bush Ave.

Cody Bird, Planning Director, introduced the item. He explained public hearing procedure and asked if there were any conflicts of interest or ex parte communications. There were no ex parte communications. Commissioner Stringer said that he knows Mr. Daren Roberson, the developer of

the property, in a professional capacity, but has no financial stake in this project.

Bird invited Brittany Lenoir, Planner III to present the staff report. Lenoir outlined the project.

Chair Sartor asked Bird about the letter attached in the packet. Bird said that the letter was from the Fait Family Partnership, who own approximately 186 acres south of County Road 58 and adjacent to the Sage Farms development. The letter asked for planning considerations that Staff typically evaluate, including drainage, traffic impact, and utility design. Staff has met with the Fait family in the past. Commissioner Whitehouse asked if that land was held in a conservation easement. Bird said that it is held under a 40 year conservation easement, with 17 years left. Commissioner Chollet asked if there would be a dedication to Poudre School District. Bird said that the school district had asked for cash in lieu of land.

Chair Sartor asked Mr. Roberson to the podium. Sartor asked Roberson what he envisioned for some of the smaller lots. Roberson said that his company has worked with Baessler Homes and other builders to build smaller, more affordable homes. The development would feature a mixture of multifamily homes and single-family homes on a wide variety of lots.

Commissioner Carman asked Roberson if he could describe the units more specifically. Roberson said he envisioned 1–2-bedroom single family homes, sometimes ranch, sometimes multistory, with garages. The cost to build street and utility infrastructure is flat, so the more units are on a block, the lower the average home cost is.

Commissioner Chollet asked if Roberson and Staff had considered multi-family homes as part of Phase 1 of the development. Roberson said that he hopes to build multi-family homes on some of the outlots, contingent on infrastructure considerations. Bird said that Staff and the developer envisioned the land in Phase 1 as single-family homes, with multi-family homes on the outlots. Commissioner Carman expressed that he believes prioritizing commercial development is important for the Town. Carman asked about the irrigation status of the development. Roberson said there would be two wells for nonpotable water as well as an irrigation canal supplied by North Poudre Irrigation Company as a contingency plan.

Commissioner Chollet asked if the traffic could necessitate a traffic signal at GW Bush Ave. Roberson said that previous development already necessitated that. Bird confirmed this and said the Town has had conversations with CDOT.

Chair Sartor opened the Public Hearing at 7:14.

Adam Albrecht, 669 Cranesbill St, asked if the regional park proposed in the south of Sage Farms could be moved further north to better serve existing residents. He also expressed that the park could be difficult to access for residents east of the railroad.

Chair Sartor closed the Public Hearing at 7:16.

Roberson said that the sewage and drainage in the south of the development make it hard to construct basements, which is why the park is proposed in that area. Bird mentioned that Staff had agreed with Roberson and his company that Roberson would meet part of Sage Farm's open space dedication requirements by purchasing 13 acres by Jefferson Ave and the railroad crossing. This would form a centrally located park to better serve existing neighborhoods.

Commissioner Whitehouse moved to forward a recommendation to the Board of Trustees to approve the preliminary plat for Sage Farms Filing 1, as presented, based on the Findings for Approval.

Commissioner McCaffrey seconded.

Yeas – Chollet, Stringer, Sartor, McCaffrey, Knaack, Whitehouse, Carman Nays-

Motion carried.

B. Proposed Amendment to the Text of Section D.2.B. of the Approved Sage Farms Planned Unit Development (PUD)

Bird asked if there were any conflicts of interest or ex parte communications regarding this item. There were none. Bird presented the proposed text amendment to the Commissioners.

Commissioner Chollet asked when the setbacks were approved for the PUD. Bird said they were approved when the PUD was approved in January, 2024. Chollet asked if there was any potential risk regarding the setbacks. Bird said they met the building code and did not see any particular risk.

Chair Sartor opened the Public Hearing at 7:40.

There was no comment.

Chair Sartor closed the Public Hearing at 7:40.

Commissioner Chollet moved to forward a recommendation to the Board of Trustees to approve the proposed text amendments to the Sage Farms PUD, as presented, based on the Findings for Approval.

Commissioner Stringer seconded.

Yeas – Chollet, Stringer, Sartor, McCaffrey, Knaack, Whitehouse Nays—Carman Motion carried.

7. COMMUNICATIONS

A. 1st Quarter 2025 Residential Building Permit and Lot Inventory Report

Bird presented the Building Permit and Lot Inventory Report.

8. ADJOURNMENT

Chairman Sartor adjourned the regular meeting at 7:50 PM

Approved this 2nd day of June, 2025.

Recording Secretary



Planning Commission Meeting

Date: June 2, 2025

Submitted Cody Bird, Planning Director

By:

Subject: Public Hearing considering a Final Plat for Wellington Business Center, Amendment No.

1

EXECUTIVE SUMMARY

Lot 7 & Lot 8, Wellington Business Center, is proposed for commercial development. A site development plan including four multi-tenant commercial buildings proposed to be constructed in phases was considered and approved by the Planning Commission at its meeting of October 7, 2024. The site development plans were considered concurrently with a preliminary plat for the property to make adjustments to public utility easement dedications and align the property lines and easement dedications with the proposed development plan. The preliminary plat was recommended for approval by the Planning Commission and the Board of Trustees. The applicant subsequently addressed required comments and revisions are reflected on the final plat. In review of the final plat, Town staff and outside referral agencies requested minor adjustments to plat text, easement width, labels and signatures/certifications on the final plat. The proposed revisions are minor in nature and will not result in any substantive changes affecting the final plat. Town staff recommends that the final plat meets the Findings for Approval and recommends approval of the final plat subject to staff comments. The Planning Commission's recommendation on the final plat will be forwarded to the Board of Trustees for consideration at a public hearing scheduled for June 10, 2025.

BACKGROUND / DISCUSSION

Background:

- The owner/developer of Lots 7 and 8, Wellington Business Center, located south of Wine Cup Street and west of I-25 Frontage Road (location map attached) has submitted a request for final plat approval to facilitate commercial development of the property.
- The Planning Commission approved a site development plan and concurrently approved a preliminary plat at its regular meeting of October 7, 2024.
 - o All site plan changes requested by the Planning Commission have been addressed in the revised site plans.
 - o The site layout and utility plan are included in this report for reference.
- The property is zoned C-3 Mixed-Use Commercial. The C-3 zone district allows a wide range of business, office, retail, restaurant and service-related uses. The proposed multiple tenant buildings can accommodate uses suitable and allowed within the district, and the lot layout and dimensions meet the district requirements of the C-3 zone district.
- The site is proposed to be developed in phases. The attached Site Phasing Plan identifies the proposed phases.
 - o A sidewalk connecting the development to Globeflower St. is proposed as part of Phase 1A to meet the pedestrian connection until the later phases are constructed.
 - o A turn lane on the I-25 Frontage Road is required to be constructed as part of Phase 2.
- The phasing plan and obligations for construction of public improvements needed to serve the development will be included as part of Development Agreement. Development Agreements are reviewed by the Board of Trustees.



- The request for final plat was advertised for public hearing for the June 2 Planning Commission meeting.
- No written or verbal public comments have been received at the date of this report.
- The Planning Commission will need to consider any testimony presented during the public hearing for the final plat.

Final Plat Process and Findings for Approval:

- A final plat request is submitted to Town staff for review in accordance with Section 15-2-170 of the Land Use Code. Town staff reviews the final plat, general development information, construction plans and profiles, structure details, sewage collection and water supply plans, drainage, grading, soils report, street lighting, and landscaping, as well as any relevant covenants and agreements.
- Town staff reviews the final plat and supporting documentation and presents the final plat and findings to the Planning Commission. The Planning Commission makes a recommendation to the Board of Trustees for consideration.
- In reviewing a final plat, the Planning Commission considers the Findings for Approval, Subsection 15-2-170(f)(3)(g) below:
- 1. The final plat conforms with the approved preliminary plat and incorporates recommended changes, modifications and conditions attached to the approval of the preliminary plat unless otherwise approved by the Board of Trustees.
- 2. The development will substantially comply with the design and development standards as set forth in Article 5 of this Code.
- 3. All applicable technical standards have been met.
- In consideration of a final plat application, the Planning Commission makes a recommendation that is forwarded to the Board of Trustees. The Planning Commission may make one of the following recommendations:
- 1. Recommend approval of the final plat;
- 2. Recommend approval of the final plat with conditions;
- 3. Recommend denial of the final plat application.

The Planning Commission's recommendation will be forwarded to the Board of Trustees for a public hearing advertised and scheduled for June 10, 2025.

Staff Comments (Site Development Plan):

The Findings for Approval for a preliminary plat are listed below along with Staff's recommendation for each finding.

Findings for Approval (Land Use Code Subsection 15-2-120(c)):

1. The final plat conforms with the approved preliminary plat and incorporates recommended changes, modifications and conditions attached to the approval of the preliminary plat unless otherwise approved by the Town Board.



- The final plat is substantially similar to the approved preliminary plat. The applicant has addressed the conditions discussed during the preliminary plat, including:
- Easement lines were adjusted to encompass water meter pits for Town public infrastructure as required.
- Sidewalks were added to the phasing plan to meet pedestrian access requirements.

2. The development will substantially comply with the Design and Development Standards as set forth in Article 5 of this code.

- Adequate space for required landscape buffers and screening are satisfied on the plat.
- The plat is compliant with applicable site access and circulation standards and dedicates appropriate access easements.
- No additional street right-of-way dedication is required to meet street and turn lane requirements.
- There are no park and open space dedication requirements for commercial development projects.
- Other applicable standards of Article 5 were evaluated and found to be compliant with the site development plan approval.

3. All applicable technical standards have been met.

- The Town Engineering Division and Public Works Staff reviewed and determined the Final Plat and required public infrastructure meets Town Standards. Minor redline changes are required on the final plat to adjust a Town water and sewer line easement to ensure it is exclusive (no other utilities allowed within the Town easement) and to adjust the width from 40 ft. to 30 ft. to allow space for other utilities.
- Text amendments are needed on the Ownership Certificate to reflect appropriate business entity names and signature authorities, and to remove a duplicate Attorney Certification. Names and Titles of Town signatures are also requested to be included below signature lines on the Final Plat.
- Labels on adjacent lots to the north need to be updated to "Wellington Business Center."
- Additional easement dedication language was requested by Xcel Energy that should be incorporated on the Final Plat.
- CDOT has verified that their standards are satisfied for Phase I. CDOT has issued an access permit for Phase I and identified that a turn lane will be required for Phase 2. The Phase 2 turn lane requirement will be included in the Development Agreement.
- Requirements of Article 6 of the Land Use Code (Subdivision Regulations) have been satisfied.

STAFF RECOMMENDATION

The Planning Commission should conduct a public hearing to receive information describing the request for replat, hear from the applicant and Town staff, and hear public testimony for the final plat.

Based upon the above findings and the staff report comments, Town staff recommends the final plat satisfies the Findings for Approval in accordance with the Land Use Code. Town staff recommends approval of the final plat subject to staff comments and redlines.

Below is the recommended motion for approval of the Final Plat:

• Move to forward a recommendation to the Board of Trustees to approve the Final Plat for Wellington Business Center, Amendment No. 1 with conditions of approval.

ATTACHMENTS



- 1. Location Map
- 2. Final Plat - Wellington Business Center, Amendment No. 1
- 3.
- Site Phasing Plan
 Site Layout and Utility Plan
 Presentation Slides 4.
- 5.

Location Map Lot 7 and Lot 8, Wellington Business Center



WELLINGTON BUSINESS CENTER, AMENDMENT NO. 1

REPLAT OF LOTS 7 AND 8, WELLINGTON BUSINESS CENTER, SITUATED IN THE NE 1/4 OF SECTION 9, TOWNSHIP 8 NORTH, RANGE 68 WEST OF THE 6TH P.M. TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADO

LEGAL DESCRIPTION

A PARCEL OF LAND SITUATED IN THE TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADO, WITHIN THE NORTHEAST QUARTER OF SECTION 9, TOWNSHIP 8 NORTH, RANGE 68 WEST OF THE 6TH PRINCIPAL MERIDIAN BEING MORE PARTICULARLY DESCRIBED

LOTS 7 AND 8, WELLINGTON BUSINESS CENTER, AT RECEPTION NUMBER 20150075922

THE ABOVE DESCRIBED PARCEL OF LAND CONTAINS 421,467 SQUARE FEET OR 9.676 ACRES, MORE OR LESS, AND IS SUBJECT TO ALL EASEMENTS AND RIGHTS-OF-WAY NOW RECORD OR EXISTING.

DEDICATION OF PUBLIC PROPERTY

THE OWNER OF THE REAL PROPERTY DESCRIBED IN THIS PLAT HAS CAUSED THE REAL PROPERTY TO BE SURVEYED, LAID OUT AND SUB-DIVIDED UNDER THE NAME OF WELLINGTON BUSINESS CENTER, AMENDMENT NO. 1, AND DOES HEREBY SELL, GRANT, DEDICATE, AND CONVEY TO THE TOWN OF WELLINGTON IN FEE SIMPLE, FREE AND CLEAR OF ALL LIENS AND ENCUMBRANCES, AND SET APART ALL OF THE STREETS, ROADS, ALLEYS, EASEMENTS, AND OTHER PUBLIC WAYS AND PLACES, AS SHOWN ON THE ACCOMPANYING PLAT TO USE OF THE PUBLIC FOREVER. THE OWNER SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF ALL IMPROVEMENTS OF SAID STREETS, ALLEYS, EASEMENTS, PUBLIC WAYS AND PLACES, UNTIL ACCEPTANCE OF MAINTENANCE THEREFOR BY THE TOWN AS PROVIDED IN WELLINGTON MUNICIPAL CODE.

CERTIFICATE OF TITLE

I, ______, AN ATTORNEY LICENSED TO PRACTICE LAW IN THE STATE OF COLORADO, CERTIFY TO THE TOWN OF WELLINGTON, COLORADO, THAT I HAVE EXAMINED THE TITLE TO THE PROPERTY BEING SUBDIVIDED AND BEING DEDICATED TO THE TOWN OF WELLINGTON, COLORADO AND THAT TO THE EXTENT SHOWN OF RECORD IN THE REAL ESTATE RECORDS IN THE CLERK AND RECORDER'S OFFICE OF LARIMER COUNTY, COLORADO OR ACTUALLY KNOWN BY ME TO EXIST, ALL OWNERS AND PROPRIETORS AS DEFINED BY C.R.S. 31_23_111 HAVE SIGNED THIS PLAT.

ATTORNEY	REGISTRATION NO.

CERTIFICATE OF OWNERSHIP


I CERTIFY THAT FRS PROPERTIES LLC, A COLORADO LIMITED LIABILITY COMPANY, IS THE OWNER OF THE PROPERTY, THERE ARE NO MORTGAGEES AND HOLDER OF LIENS UPON THE PROPERTY, AND EACH AND ALL HEREBY CONSENT TO THIS PLAT AND JOIN IN THE CONVEYANCE AND DEDICATION OF ALL STREETS, ROADS, ALLEYS, EASEMENTS, PUBLIC WAYS, AND PLACES SHOWN HEREON.

EXECUTED THIS _	DAY OF	A.D. 20

OWNER:	FRS PROPERTIES LLC, A COLORADO LIMITED LIABILITY COMPANY
NAME:	
TITLE:	
STATE OF	
COUNTY	DF)
THE FORE	GOING DEDICATION WAS ACKNOWLEDGED BEFORE ME THIS DAY OF
	A.D. 20

WITNESS MY HAND AND SEAL

MY COMMISSION EXPIRES




PLAT NOTES:

- 1. A BLANKET GRADING, DRAINAGE AND ACCESS EASEMENT IS HEREBY DEDICATED ACROSS LOTS 1 AND 2 OUTSIDE OF THE BUILDING EXCLUSION EASEMENTS.
- 2. RIDGETOP ENGINEERING AND SURVEYING DOES NOT HAVE THE EXPERTISE TO ADDRESS MINERAL RIGHTS, AND RECOMMENDS THE OWNER RETAIN AN EXPERT TO ADDRESS THESE MATTERS. RIDGETOP ENGINEERING AND SURVEYING ASSUMES NO RESPONSIBILITY FOR THE MINERAL RIGHTS UPON THIS TRACT OF LAND.
- 3. THIS LAND SURVEY DOES NOT CONSTITUTE A TITLE SEARCH BY RIDGETOP ENGINEERING AND SURVEYING. FOR ALL INFORMATION REGARDING EASEMENTS, RIGHTS-OF-WAY, OR TITLE OF RECORD, RIDGETOP ENGINEERING AND SURVEYING RELIED ON THE PROPERTY INFORMATION BINDER, BY LAND TITLE GUARANTEE COMPANY, ORDER NUMBER: FC1F25211222, DATED APRIL 24, 2024 AT 5:00 P.M.
- 4. THE LINEAL UNIT USED IN THE PREPARATION OF THIS SURVEY IS THE U.S. SURVEY FOOT AS DEFINED BY THE UNITED STATES DEPARTMENT OF COMMERCE, NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY
- 5. BASIS OF BEARINGS: BASED ON THE EAST LINE OF THE NORTHEAST 1/4 OF SECTION 9, TOWNSHIP 8 NORTH, RANGE 68 WEST OF THE 6TH P.M., WITH A BEARING OF SOUTH 00°46'46" WEST, MONUMENTED AT THE NORTH BY A 3-1/4" ALUMINUM CAP IN RANGE BOX STAMPED, "COLORADO DEPARTMENT OF HIGHWAYS," PLS 12374, AND MONUMENTED AT THE SOUTH BY A -1/4" ALUMINUM CAP IN RANGE BOX STAMPED, "COLORADO DEPARTMENT OF HIGHWAYS," PLS 12374, WITH ALL OTHER BEARINGS CONTAINED HEREIN RELATIVE THERETO.
- 6. BY GRAPHIC PLOTTING ONLY, THE SUBJECT PROPERTY IS LOCATED WITHIN ZONE X, AREA OF MINIMAL FLOOD HAZARD, AS ESTABLISHED BY FEMA PER FIRM PANEL NUMBER 08069C0767F, EFFECTIVE DATE: DECEMBER 19, 2006.

APPROVED THIS	DAY OF	, 20	, BY THE TOWN PLANNI
AND ZONING COMMISSI	ON, WELLINGTON, COLOR	ADO.	
AS:			
	TEES CERTIFICATE	-	
	TEES CERTIFICATE	-	, BY THE BOARD OF
APPROVED THIS	DAY OF	, 20	
APPROVED THIS TRUSTEES, WELLINGTO	DAY OF	, 20, OVAL IS CONDITIO	ONED UPON ALL EXPENSES
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY	DAY OF	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS,	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS,	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS,	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS,	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS, FINANCED BY OTHERS	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS AND NOT THE TOWN.	, 20, 20 OVAL IS CONDITION. UTILITY SERVICE S, STREET SIGNS	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS, FINANCED BY OTHERS A	DAY OF	, 20, 20, 20, 20, 20, OVAL IS CONDITIONS. UTILITY SERVICE S, STREET SIGNS.	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS, FINANCED BY OTHERS A	DAY OFDAY OFDN, COLORADO. THIS APPROVEMENTS FOR ALL GUTTERS, STREET LIGHTS AND NOT THE TOWN.	, 20, 20, 20, 20, 20, OVAL IS CONDITIONS. UTILITY SERVICE S, STREET SIGNS.	ONED UPON ALL EXPENSES ES, PAVING, GRADING,
APPROVED THIS TRUSTEES, WELLINGTO INVOLVING NECESSARY LANDSCAPING, CURBS, FINANCED BY OTHERS A	DAY OF	, 20, 20, 20, 20, 20, OVAL IS CONDITIONS. UTILITY SERVICE S, STREET SIGNS.	ONED UPON ALL EXPENSES ES, PAVING, GRADING,

SURVEYORS CERTIFICATE

I, MICHAEL DAVID LANG, PLS 37053, A DULY REGISTERED LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THIS PLAT OF WELLINGTON BUSINESS CENTER, AMENDMENT NO. 1 WAS PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT THIS PLAT HAS BEEN PREPARED IN COMPLIANCE WITH ALL APPLICABLE LAWS OF THE STATE OF COLORADO AT THE TIME OF THIS SURVEY AND WITHIN MY CONTROL AND IS ACCURATE TO THE BEST OF MY KNOWLEDGE INFORMATION AND BELIEF.




ATTORNEY'S CERTIFICATION


I, ______, AN ATTORNEY LICENSED TO PRACTICE LAW IN THE STATE OF COLORADO, CERTIFY TO THE TOWN OF WELLINGTON, COLORADO, THAT I HAVE EXAMINED THE TITLE TO THE PROPERTY BEING SUBDIVIDED AND BEING DEDICATED TO THE TOWN OF WELLINGTON, COLORADO, AND THAT ALL OWNERS AND PROPRIETORS AS DEFINED BY CRS 31-23-111 HAVE SIGNED OR RATIFIED THIS PLAT.


ATTORNEY:	
ADDRESS:	
ADDITIEGO:	
REGISTRATION NO.:	


SARDEN DRIVE SITUATED IN THE NE 1/4 OF SITUATED IN THE SITUATE














Planning Commission Regular Meeting

Final Plat for Wellington Business Center, Lots 7 & 8

Presented By: Cody Bird, Planning Director Town of Wellington Planning Department

Monday, June 2, 2025



SITE LOCATION MAP






Application Background

- The Planning Commission approved a site development plan for the property October 7, 2024.
- A preliminary plat to align property lines and easement dedications was also considered and approved at the October 7, 2024 meeting.
- Requested changes to the site development plan and preliminary plat are reflected on the Final Plat drawing.




Final Plat





Phasing Plan





Findings For Approval – Final Plat

- 1. The final plat conforms with the approved preliminary plat and incorporates recommended changes, modifications and conditions attached to the approval of the preliminary plat unless otherwise approved by the Town Board.
- 2. The development will substantially comply with the Design and Development Standards as set forth in Article 5 of the Land Use Code.
- 3. All applicable technical standards have been met.



Staff Recommendation

Staff recommends that the Findings or Approval are satisfied, and recommends approval of the Final Plat.

Minor revisions on the Plat are recommended as a condition of approval:

- Updating Owner Certification
- Updating Attorney Certification
- Correcting labeling
- Modifying easement dedication language
- · Modifying a Town water and sewer easement to be exclusive and adjust width



Staff Recommendation

Recommended Motion:

Move to forward a recommendation to the Board of Trustees to approve the final plat for Wellington Business Center, Amendment No. 1 with conditions of approval.



Questions or Comments?





Planning Commission Meeting

Date: June 2, 2025

Submitted Aidan Checkett, Planner 1

By:

Subject: Review of Amended Site Development Plans for Lots 1 and 2, Block 2, Bonfire Subdivision

2nd Filing

EXECUTIVE SUMMARY

BACKGROUND / DISCUSSION

Background:

- Kaufman & Robinson Inc. is the owner of the property at 4102 and 4134 Glow Ave, Wellington CO.
- The Planning Commission previously approved a site development plan for this project on November 7, 2022. Plan approvals are valid for a period of three years (approval expires November 7, 2025).
- The owner has submitted a development plan application to amend the previous approved site development plan.
- The applicant has also applied for a lot-line adjustment to combine the two lots before beginning construction on the site. The review will be dependent on the amended site development plan. Lot-line adjustments are reviewed administratively [Sec. 15-2-90(c)(3)].
- Changes to approved site development plans that exceed 10% of any measurable standard require Planning Commission review and approval [(Sec. 15-2-120(c)].
 - The applicant is proposing to increase the building height from 28 ft. for the prior approval to 37 ft. The height increase exceeds 10% that can be approved administratively, and requires review by the Planning Commission.
 - Other changes to the site plan include a slight increase to the building footprint and minor changes to landscaping, parking, and illumination.
 - o Review of an amendment to an approved site development plan should consider the elements of the site development plan that are different from the approved plan.

Site Development Plan Process and Findings for Approval:

- A site development plan review request is submitted to Town staff for review in accordance with Section 15-2-120 of the Land Use Code. Town staff reviews the site development plan drawings, engineering design, traffic considerations, landscaping plan, site lighting plan and building design and materials in accordance with applicable development standards.
- Town staff reviews the site development plan drawings and coordinates with the applicant and designers to address needed design criteria and development standards. The site development plan is presented to the Planning Commission for consideration.
- In reviewing a site development plan, the Planning Commission considers the Findings for Approval, Section 15-2-120(c) below:
 - 1. The site development plan is consistent with the Comprehensive Plan and the intent stated in this Land Use Code.
 - 2. The lot size and lot dimensions are consistent with what is shown on the approved final plat.



- 3. No buildings or structures infringe on any easements.
- 4. The proposed site grading is consistent with the requirements of any applicable adopted storm drainage criteria or master drainage plans.
- 5. The density and dimensions shown conform with Article 4 of this Code or the approved PUD requirements.
- 6. The applicable development standards have been adequately addressed and the proposed improvements conform with Article 5 of this Code.
- In consideration of a site development plan, the Planning Commission makes the final approval decision. The Planning Commission may take one of the following actions:
 - 1. Approve the site development plan;
 - 2. Approve the site development plan with conditions;
 - 3. Deny the site development plan application.

Staff Comments

The Findings for Approval for a site development plan are listed below along with Staff's recommendation for each finding. Findings for Approval (Land Use Code Subsection 15-2-120(c)):

1. The site development plan is consistent with the Comprehensive Plan and the intent stated in this Land Use Code.

- The property is zoned Light Industrial and is designated as Industrial in the Comprehensive Plan Future Land Use Map. The proposed uses (professional office, light industrial and manufacturing, and wholesale distribution, warehousing, and storage) are all permitted within the Light Industrial district.
- The Planning Commission previously made this finding for the November 7, 2022 approval. The proposed use of the property has not changed, therefore this finding is consistent with the Comprehensive Plan and Land Use Code.
- 2. The lot size and lot dimensions are consistent with what is shown on the approved final plat.
 - The lot size and lot dimensions have not changed from the previously approved site development plan.
 - The property will need a lot-line adjustment, as indicated in the staff report for the November 7, 2022 site plan. The applicant intends to submit this after site development plan approval. Lot-line adjustments are reviewed and approved administratively [Section 15-2-90].
- 3. No buildings or structures infringe on any easements.
 - Easements for drainage, utilities, construction, and access will be dedicated by separate instrument and are identified on the site plan drawings. The proposed structure does not infringe on any of these easements.
- 4. The proposed site grading is consistent with the requirements of any applicable adopted storm drainage criteria or master drainage plans.
 - There are no changes proposed to the drainage plans from the approved site development plan.
 - The Town Engineering Division and Public Works Department has reviewed the proposed site development plan and construction sheets. They found the drainage to meet their criteria and had no further comments.
- 5. The density and dimensions shown conform with Article 3 of this Code or the approved PUD requirements.
 - Density and dimensional criteria are satisfied and are further detailed below:



- There are no residential units proposed for this development, so residential density is not applicable.
- The floor area ratio for the LI zoning district is 1:1 (meaning the building area, all floors, is equal to the lot area). The building footprints, including proposed mezzanines, are less than the floor area ratio of 1:1 and this criterion is satisfied.
- Required setbacks for Front Yard (25 feet), Rear Yard (10 feet) and Side Yard (10 feet) are satisfied.
- The maximum building height is proposed to increase from 28 ft to 37 ft. The new proposed height is less than the maximum allowed for the Light Industrial district (45 ft) and meets the requirement.
- PUD requirements are not applicable to this property.

6. The applicable development standards have been adequately addressed and the proposed improvements conform with Article 5 of this Code.

• The amended site development plans are in substantial compliance with Article 5, Development Standards, of the Land Use Code, including but not limited to the following provisions:

• Exterior Lighting:

• There have been minor changes made to the illumination of the site. Additional light fixtures were added in the northwest corner of the building and locations of fixtures on the east side of the building were changed slightly. Illumination is still in compliance with the Town's standards. Lighting meets the minimum and maximum foot-candle requirements.

• Landscaping and Screening:

• There have been minor changes made to the landscaping plans. Landscaping was reconfigured along the south façade of the building. A landscape buffer was added along the west side of the western parking lot, and two landscape islands further west were removed. The site is in compliance with buffer requirements, parking island requirements, and industrial landscaping requirements. Some of the perimeter screening and landscaping requirements may be relaxed for the east side of the property where the shared property line is with another light industrial use.

• Parking and Loading:

 There are minor changes in the location of parking spots to the southwest of the building based on changes to the building footprint. The total number of parking spaces and ADA accessible parking spaces is unchanged.

• Site and Building Design:

- o The height of the building was increased to 37 feet. It is less than the district maximum of 45 feet.
- There were minor changes to the building layout (orientation and location of doors, a slight change to the building footprint). The building itself is not proposed to change in size.

• Utilities:

 The Engineering Division and Public Works Department reviewed the proposed site development plan and did not identify any notable changes to the utility plans. They have recommended some minor changes to labels, references and standard details on the civil construction plans.

• Transportation and Connectivity:

 Driveways and circulation aisles are the same as the originally approved plan. No additional changes are needed.



STAFF RECOMMENDATION

Town staff have identified redline comments on the site development plan. The applicant is required to revise the site development plan documents to incorporate all corrections, comments and/or conditions, including Town engineering review of the civil plans, and submit revised copies to the Town.

Based upon the above findings and the staff report comments, Town staff recommends the amended site development plan satisfies the Findings for Approval in accordance with the Land Use Code, and is consistent with the November 7, 2022 approved plans/ Town staff recommends approval of the amended site development plan subject to the following conditions:

- 1. Addressing Planning comments
- 2. Addressing Public Works / Engineering comments and redlines

Below is the recommended motion:


1. Move to approve the amended site development plan for Lot 1 and Lot 2, Bonfire Subdivision Filing 2 with conditions of approval.

ATTACHMENTS

- 1. Location Map
- 2. KRI Amended Site Development Plan
- 3. Presentation Slides



Lot 1A KRI Bonfire F-3 Site Map



SITE DEVELOPMENT PLAN

KRI WELLINGTON - LOT 1A BONFIRE SUB 3RD FILING

LOT 1A, BLOCK 2, BONFIRE SUBDIVISION 2RD FILING LOT LINE ADJUSTMENT

BEING AN ADMINSITRATIVE REPLAT OF LOTS 1 & 2, BLOCK 2 OF BONFIRE SUBDIVISION, 2ND FILING

LOCATED IN PART OF THE SOUTHEAST QUARTER OF SECTION 27 TOWNSHIP 9 NORTH, RANGE 68 WEST OF THE 6TH PRINCIPAL MERIDIAN
TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADO

SIGNATURE BLOCK:

TOWN PLANNING DIRECTOR

DATE

PUBLIC WORKS DIRECTOR

DATE

DATE

TOWN ENGINEER

FIRE DEPARTMENT DATE

SURVEYOR SEAL / STAMP DATE

V CR 99 WASHINGTON AVE

PROJECT PURPOSE/DESCRIPTION:

THIS PROJECT PROPOSES AN INDUSTRIAL DEVELOPMENT THAT IS ALIGNED WITH ADJACENT USES AND NEIGHBORHOOD NEEDS. LANDSCAPING AND ARCHITECTURE WILL COMPLIMENT THE LOCAL ECOLOGY AND EXISTING DEVELOPMENT. PARKING IS PROVIDED PER TOWN OF WELLINGTON CODES.

LEGAL DESCRIPTION:
BONFIRE SUBDIVISION 3RD FILING, BEING A REPLAT OFLOTS 1 & 2, BLOCK 2
OF BONFIRE SUBDIVISION, 2ND FILING
LOCATED IN PART OF THE SOUTHEAST QUARTER OF SECTION 27 TOWNSHIP 9
NORTH, RANGE 68 WEST OF THE 6TH PRINCIPAL MERIDIAN
TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADO

VICINITY MAP

TOTAL:

SITE DATA:

EXISTING ZONING: LI - LIGHT INDUSTRIAL
PROPOSED ZONING: LI - LIGHT INDUSTRIAL
ADJACENT ZONING: S=LI; W=O (County); E=LI:
N=O (County)
ADJACENT USES: LI - LIGHT INDUSTRIAL

SITE SF & ACREAGE: 235,362 SF / 5.4032 ACRES REQUIRED SETBACKS:

FRONT: 25' SIDE: 10' REAR: 10'

LAND USE DATA: BUILDING FOOTPRINT: 40,217 IMPERVIOUS SURFACES: 40,060 LANDSCAPE AREA (ON-SITE): 155,946

155,946

17.09%

17.25%

65.66%

100.00%

235,362 SF

49,083 SF

BUILDING DATA: BUILDING FOOTPRINT 40,217 SF OFFICE AREA: 5,004 SF **CONFERENCE AREA:** 2,302 SF 26,993 SF WAREHOUSE AREA: ACCESSORY USE: 14,784 **BUILDING HEIGHT:** VARIES, MAX HEIGHT 37' 2 STORIES MAX BUILDING HEIGHT ALLOWED PER CODE 45'-0"

PARKING SUMMARY:

TOTAL # EMPLOYEES (MAXIMUM): 55

TOTAL EMPLOYEE PARKING SPACES REQUIRED / PROVIDED: 55 / 58

(1 SPACE PER EMPLOYEE PER CODE)

BICYCLE PARKING REQUIRED / PROVIDED: 2 / 2

ADA SPACES REQUIRED / PROVIDED: 3 (1 VAN ACCESSIBLE) / 3

TOTAL PARKING SPACES REQUIRED / PROVIDED: 55 / 59

SHEET INDEX:

- 1. COVER PAGE
- 2. SITE PLAN
- 3. BUILDING ELEVATIONS AND PERSPECTIVES
- 4. BUILDING ELEVATIONS AND PERSPECTIVES TRASH
- 5. ARCHITECTURAL MATERIAL BOARD
- 6. HORIZONTAL CONTROL PLAN
- 7. UTILITY PLAN
- 8. GRADING PLAN
- 9. EROSION CONTROL PLAN
- 10. DRAINAGE PLAN
- 11. LANDSCAPE PLAN
- 12. LANDSCAPE PLAN DETAILS AND NOTES
- 13. IRRIGATION PLAN
- 14. IRRIGATION PLAN DETAILS
- 15. PHOTOMETRIC PLAN
- 16. PHOTOMETRIC PLAN DETAILS & NOTES

DEVELOPMENT TEAM:

OWNER / DEVELOPER:
KAUFMAN & ROBINSON, INC.
1330 BLUE SPRUCE DRIVE
FORT COLLINS, CO 80524
TEL: 970-495-0187
E-MAIL: guidotti@ionsources.com
CONTACT: CHRIS GUIDOTTI

ARCHITECT:
INFUSION ARCHITECTS
206 E 4TH STREET
LOVELAND, CO 80537
CONTACT: DARIO BARCENA

PLANNER / LANDSCAPE ARCHITECT:
PHOENYX LANDSCAPE ARCHITECTURE, LLC
JASON R OLDHAM
jason@phoenyxla.com
970-420-9555

970 631 2671 (CELL)

TOTAL SF:

CIVIL ENGINEER:
MICHAEL P. OBERLANDER, PE
OPERATIONS MANAGER, NORTHERN COLORADO
WILSON & COMPANY, INC., ENGINEERS & ARCHITECTS
970 834 6365 (DIRECT)

DATE: 04.01.25
SCALE: See Sheet
DRAWN: JRO
CHKD BY: JO
SHEET

BUILDING


N O

PROJECT COVER SHEET

1 of 16

PLAN NOTES


- 1. REFER TO UTILITY PLANS FOR ALL UTILITY, DRAINAGE, GRADING, EROSION CONTROL AND STREET DESIGN REQUIREMENTS.
- 2. PARKING LOT LIGHTING IS TO BE DESIGNED AS "FULL CUT-OFF".
- 3. ALL SIGNS SHALL COMPLY WITH THE TOWN OF WELLINGTON SIGN REGULATIONS / SIGN PERMIT REQUIREMENTS.
- 4. SEE CIVIL PLANS FOR PAVEMENT TYPES AND DEPTHS.
- 5. THE CONTRACTOR SHALL NOT PURPOSEFULLY PROCEED WITH ANY CONSTRUCTION PER PLANS PROVIDED WHEN OBSTRUCTIONS AND / OR DIFFERENCES EXIST THAT WERE NOT CONSIDERED AND REVIEWED OR APPROVED. CONTRACTOR SHALL NOTIFY OWNER OR OWNER'S REPRESENTATIVE AND THE TOWN OF WELLINGTON IF SITUATION ARISES AND REVISIONS ARE NECESSARY.
- 6. THE CONTRACTOR SHALL PREVENT SEDIMENT, DEBRIS AND OTHER POLLUTANTS FROM ENTERING ANY STORM WATER SEWER SYSTEM OR, ADJACENT WATER WAYS, ETC., DURING THE DEMOLITION OR CONSTRUCTION OPERATIONS THAT ARE PART OF THIS PROJECT. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE EXPENSE OF CORRECTION OF ANY ADVERSE IMPACTS TO THE STORM WATER SEWER SYSTEM OR ADJACENT WATER WAYS, WETLANDS ETC., RESULTING FROM THE WORK DONE AS PART OF THIS PROJECT/CONTRACT.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE PRIOR TO BIDDING AND CONSTRUCTION, OF BECOMING AWARE OF ALL EXISTING AND PROPOSED UTILITIES, PIPES, STRUCTURES, ETC. CALL UNCC THREE DAYS BEFORE SCHEDULED WORK AT 811 OR 1~922-1987.
- 8. ALL SIGNAGE MUST BE APPROVED BY THE TOWN PRIOR TO INSTALLATION.
- 9. KNOX BOX TO BE PROVIDED BY OWNER- LOCATION TO BE DETERMINED BY WELLINGTON FIRE RESCUE AUTHORITY.



FIRE HYDRANT

SEE DISCIPLINE SHEETS FOR ADDITIONAL

INFORMATION



EXISTING CONDITIONS LEGEND =SANITARY SEWER MANHOLE =STORM MANHOLE EL =TELEPHONE PULL BOX =FIRE HYDRANT □ =ELECTRICAL TRANSFORMER

5,004 SF

2,302 SF

26,993

14,784

45'-0"

49,083

40,217

40,060

155,946

VARIES,



BUILDING GTON, KRI BL WELLING

235,362 SF

PARKING SUMMARY:

TOTAL # EMPLOYEES (MAXIMUM): 55 TOTAL EMPLOYEE PARKING SPACES REQUIRED / PROVIDED: 55 / 58 (1 SPACE PER EMPLOYEE PER CODE)

17.09%

17.25%

65.66%

100.00%

ADA SPACES REQUIRED / PROVIDED: 3 (1

TOTAL PARKING SPACES REQUIRED / PROVIDED: 55 / 59

> SHEET SITE PLAN


DRAWN: JRO

CHKD BY: JO

DATE: 04.01.25

SCALE: See Sheet

2 of 16




CONSTRUCTION

Issued For C & S PERMIT: 6/01/2021
Issued For TF PERMIT: 8/25/2021 evision Number Revision Dat

25007

4/21/2025 4:35:35 PM

3 /16





SOUTH EAST AEREAL 3D VIEW (FOR REFERENCE ONLY)



SOUTH WEST 3D VIEW (FOR REFERENCE ONLY)



EXTERIOR MATERIALS PRODUCT KEYNOTE MATERIAL MANUFACTURER COLOR NAME REMARKS PRE-FINISHED ALUMINUM CANOPY CLEAR ANODIZED ALUMINUM AT SINGLE STOREFRONTS (CANTILEVERED) PRE-FINISHED ALUMINUM CANOPY AT MULTIPLE STOREFRONT CLEAR ANODIZED ALUMINUM (CANTILEVERED) PRE-FINISHED ALUMINUM CANOPY CLEAR ANODIZED ALUMINUM AT MAIN ENTRY (CANTILEVERED) 6" CONCRETE FILLED STEEL PIPE BOLLARD TBD TO MATCH METAL WALL PANEL- SLATE GRAY PAINT TO MATCH COLOR OF SURFACE MATERIAL AT LOCATION RE: DOOR SCHEDULE DR-1 HOLLOW METAL DOOR & FRAME SLATE GRAY - SHERWIN WILLIAMS OR SIM. METAL TRASH GATE METAL PANEL METAL SALES TBD PAINT TO MATCH METAL PANEL COLOR GR-1 GURADRAIL AT 3'-6" FORM FINISH FLOOR OVERHEAD DOOR PAINT TO MATCH COLOR OF SURFACE MATERIAL AT RE: DOOR SCHEDULE C.H.I. OVERHEAD DOORS-SIM. | TBD LOCATION-GLASS TO MATCH STOREFRONT TO MATCH COLOR OF SURFACE AT LOCATION PC-1 ALUMINUM PARAPET CAP FLASHING ALUMINUM STOREFRONT WINDOW SYSTEM TBD CLEAR ANODIZED ALUMINUM PRECAST CONCRETE PANEL RE: PRECAST MFR. DRAWINGS TBD 872 WHITE CHRISTMAS - BENJAMIN MOORE OR SIM W-2 PRECAST CONCRETE PANEL WITH TEXTURE RE: PRECAST MFR. DRAWINGS TBD SLATE GRAY - SHERWIN WILLIAMS OR SIM. METAL SALES EM1-1653 OR SIM. TBD METAL WALL PANEL- SLATE GRAY RE: ROOF PLAN/ STRUCTURAL W-5 MECHANICAL SCREEN WALL SLATE GRAY - SHERWIN WILLIAMS OR SIM.


WC-1 PRECAST WALL CAP

BUILDING PROJECTIONS INCLUDING GUTTER, DOWNSPOUTS, CHIMNEYS, FLUES, VENTS SHALL MATCH IN COLOR THE PERMANENT COLOR OF THE SURFACE FOR THEY PROJECT OR MATCH THE BUILDING'S TRIM COLOR.

SIGNS ARE SHOWN FOR ILUSTRATIVE. MUST MEET THE SIGN CODE REQUIREMENTS.



VITRO OR SIM. OPTIGRAY GLASS EXTERIOR REFLECTANCE 8% INTERIOR REFLECTANCE 11%



W-5 MECHANICAL SCREEN METAL SALES EM1-1653 OR SIM.-SLATE GRAY



W-1 STRESSCON PRECAST 872 WHITE CHRISTMAS

W-2 STRESSCON PRECAST CONCRETE PANEL W/ TEXTURE - SLATE GRAY

CONSTRUCTION


Issued For C & S PERMIT: 6/01/2021
Issued For TF PERMIT: 8/25/2021


25007 4/21/2025 4:35:42 PM


ARCHITECTURAL MATERIAL BOARD


5 /16


SOUTH EAST 3D VIEW (FOR REFERENCE ONLY)














ISSUANCE:

DHOENYX

LANDSCADE

ARCHITECTUR

Professional
Landscape



BUILDING INGTON, CO

WELLINGT

DATE: 04.01.25
SCALE: See Sheet
DRAWN: JRO
CHKD BY: JO

SHEET
LANDSCAPE
PLAN

11 of 16

(Note: All references to "Contractor" are specific to "Landscape Contractor" unless notified as "General or other type of Contractor")

- CONTRACTOR IS RESPONSIBLE FOR VERIFYING QUANTITIES OF MATERIALS NEEDED TO COMPLETE THIS PLAN IN THE FIELD. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES BETWEEN THE DRAWINGS AND CONDITIONS IN THE FIELD. SUBSTITUTIONS OF PLANT MATERIAL ARE NOT ALLOWED WITHOUT APPROVAL FROM LANDSCAPE ARCHITECT AND TOWN OF WELLINGTON GIVEN PRIOR TO INSTALLATION. GRAPHIC QTY'S. PREVAIL OVER WRITTEN QTY'S. PRIOR TO COMMENCEMENT OF WORK THE LANDSCAPE CONTRACTOR SHALL CONTACT OWNERS REPRESENTATIVE FOR SPECIFIC INSTRUCTIONS RELEVANT TO THE SEQUENCING AND SCOPE OF WORK.
- 2. CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL LANDSCAPE SHOWN ON THIS PLAN. ANY DEFICIENCIES OR DEVIATIONS FROM THIS PLAN ARE TO BE APPROVED BY OWNER'S REPRESENTATIVE OR LANDSCAPE ARCHITECT. ANY CHANGES FROM THE APPROVED PLANS MAY REQUIRE APPROVAL FROM THE TOWN PLANNING DEPARTMENT. LANDSCAPE CONTRACTOR TO PROVIDE ALL LABOR AND MATERIALS NECESSARY TO FURNISH SCOPE OF WORK AS SHOWN PER PLAN.
- EXISTING TOPSOIL IS TO BE STOCKPILED AND USED TO ESTABLISH FINAL GRADES WITHIN LANDSCAPE AREAS. ALL STOCKPILED SOIL MUST BE CLEAR OF WEEDS, ROCKS AND DEBRIS BEFORE REUSE. ALL BERMED PLANTING BEDS TO BE CREATED WITH IMPORTED TOPSOIL.
- GENERAL CONTRACTOR TO RE-SPREAD STOCKPILED SOIL AND ESTABLISH ROUGH GRADE CONDITIONS TO THE FOLLOWING SPECIFICATIONS:
- A. 1" BELOW CURB FOR ALL SEEDED AREAS.
- B. 2.5" BELOW CURB FOR ALL SODDED AREAS.
- C. 4" BELOW CURB FOR ALL PLANTING, ROCK AND MULCH BEDS. CONTRACTOR TO TILL PARKING LOT ISLANDS TO A DEPTH OF 30".
- AMEND ALL PLANTING BEDS WITH CLASS 1 COMPOST. APPLY AT RATE OF 4 CYDS. PER 1000 SQUARE FEET TO ALL PLANTING BEDS AND MANICURED LAWN AREAS, AND 2 CYDS. PER 1000 SQUARE FEET FOR SEEDED AREAS. TILL, MIXING THOROUGHLY, INTO THE UPPER 8" OF SOIL.
- FINISH GRADE TO BE ESTABLISHED BY LANDSCAPE CONTRACTOR. SURFACE SHALL BE FREE OF ROCKS AND DEBRIS. FINISH GRADE IN SEED AREAS SHALL BE FREE FROM ROCKS AND DEBRIS ½" AND GREATER. FINISH GRADE IN SODDED AREAS SHALL BE FREE FROM ROCKS AND DEBRIS 1/4" AND GREATER. CONTRACTOR TO REPORT ANY POOR DRAINAGE CONDITIONS PRIOR TO CONSTRUCTION.
- CONTRACTOR IS TO PROVIDE VERIFICATION THAT ALL SOD AND SEED IS OF THE SPECIES SHOWN ON THIS PLAN. NO SUBSTITUTIONS WILL BE ALLOWED. SOD TO BE LAID WITH TIGHT STAGGERED EDGES AND BE ROLLED AFTER INSTALLATION. SEEDED AREAS CANNOT BE SUBSTITUTED WITH SOD.
- 9. MULCHS: ALL PLANTING BEDS THAT CALL FOR WOOD MULCH TO RECEIVE 4" ORGANIC SHREDDED BARK MULCH. SHREDDED MULCH IS TO BE OF FIBROUS MATERIAL, NOT CHIPS OR CHUNKS. NO FABRIC IS TO BE PLACED UNDER WOOD/ORGANIC MULCH. ALL MULCHED BEDS ARE TO BE SPRAYED WITH WATER AFTER INSTALLATION TO HELP MULCH TO MAT

ALL AREAS THAT CALL FOR COBBLE/ROCK MULCH TO RECEIVE MIN. 3" DEPTH, UNLESS NOTED OTHERWISE. USE QUICK RELEASE ORGANIC PRE-EMERGENT HERBICIDE FOR ALL MULCHED AND PERENNIAL/PLANTING BEDS (AND FOR COBBLE/AGGREGATE AREAS WITH SLOPES EXCEEDING 3:1 GRADE.

TREES IN COBBLE/ROCK MULCH, SOD AND SEEDED AREAS TO RECEIVE 4' DIAMETER OF WOOD MULCH RING, 3" DEEP. SHRUBS AND GROUNDCOVERS IN COBBLE/ROCK MULCH SOD AND SEEDED AREAS TO RECEIVE A WOOD MULCH RING AT 2X DIAMETER OF ROOT BALL, 3" DEPTH. NO FABRIC UNDERLAYMENT IN WOOD MULCH RINGS.

- 10. SEED MIX INSTALLATION: CONTRACTOR TO DRILL SEED WITH BRILLION TYPE APPLICATOR AND APPLY 'SOIL GUARD' BONDED FIBER MATRIX (BFM), WHERE INDICATED PER PLAN AND SCHEDULES. APPLY SEED IN TWO DIRECTIONS (PERPENDICULAR OF THE OTHER) ADD SOIL GUARD BFM FOR DRILL SEEDING WHERE NOTED PER PLAN AND ON ALL SLOPES 5:1 TO 3:1. FOR AREAS WITH 3:1 SLOPES OR GREATER CONTRACTOR TO USE SOIL GUARD APPLICATION ONLY (IN LIEU OF HYDROMULCH) CONTRACTOR TO SPOT SEED NON-GERMINATING AREAS (3) MONTHS AFTER INITIAL SEED APPLICATION. CONTRACTOR TO RE-SEED ALL BARE AREAS (6"x6") AND GREATER AFTER (6) MONTHS FROM SEED GERMINATION OR AT THE BEGINNING OF THE FOLLOWING GROWING SEASON. PRIOR TO THE 11-MONTH WARRANTY INSPECTION RE-APPLY SOIL GUARD AND SEED MIX TO ALL BARE AREAS (6"x6" OR GREATER) AND TO ALL BARE AREAS (4"x4" OR GREATER) ON ALL SLOPES 3:1 AND
- 11. REMOVED DEAD TWIGS AND BRANCHES FROM ALL NEW AND EXISTING PLANT MATERIAL IN A MANNER THAT DOES NOT CHANGE THE NATURAL HABIT OF THE PLANT MATERIAL. SCARES OF 1" OR MORE SHALL BE PAINTED WITH ORGANIC TREE PAINT. CENTRAL LEADERS SHALL NOT BE REMOVED AT ANY TIME. NEWLY PLANTED TREES WITHOUT CENTRAL LEADERS WILL BE REJECTED.
- 12. CONTRACTOR TO APPLY FERTILIZER IN SPRING & LATE SEPTEMBER. WATER THOROUGHLY AFTER APPLICATION OF FERTILIZERS.

ALL SEEDED AND SODDED AREAS TO HAVE RECOMMEND FERTILIZER APPLICATIONS ADDED ONCE IN MID TO LATE JUNE AND ONCE IN LATE SEPTEMBER. WATER THOROUGHLY AFTER APPLICATION OF FERTILIZERS.

- 13. ALL PLANT MATERIALS AND UTILITIES ARE SHOWN AT AN APPROXIMATE LOCATIONS. THE CONTRACTOR MAY NEED TO ADJUST LOCATIONS OF PLANT MATERIAL TO ADHERE TO SPECIFIC ON-SITE CONDITIONS AND CODE REQUIREMENTS. ALL TREES AND SHRUBS TO BE PLACES AT 2' MINIMUM BACK OF CURB. CONTRACTOR TO CALL FOR UTILITY LOCATES BEFORE PLANTING (TYP.) 1-800-922-1987, OR CALL 811 BEFORE YOU DIG!
- 14. STEEL EDGING TO BE USED TO SEPARATE ALL TURF AND/OR SEEDED AREAS FROM PLANTING BEDS. USE PERFORATED EDGING SEGMENTS TO OBTAIN POSITIVE DRAINAGE FOR ALL DRAINAGE SWALES OR AREAS OF STANDING WATER.
- 15. CONTRACTOR TO PROVIDE COBBLE & UNDERLAYMENT FOR BUILDING DRAINS AND SWALES THROUGH LANDSCAPED AREAS.
- 16. ALL REQUIRED LANDSCAPING TO BE INSTALLED PRIOR TO ISSUANCE OF THE CERTIFICATE OF OCCUPANCY.
- 17. ALL NURSERY STOCK TO CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI z60.1) AND THE COLORADO NURSERY ACT.
- 18. CONTRACTOR IS RESPONSIBLE FOR CONTACTING LANDSCAPE ARCHITECT FOR ALL REQUIRED INSPECTIONS. PROVIDE AT LEAST 48 HOURS NOTICE TO SCHEDULE AN INSPECTION. REQUIRED INSPECTIONS INCLUDE A LANDSCAPE LAYOUT AND PLANT MATERIAL VERIFICATION AND PLACEMENT INSPECTION, IRRIGATION MAIN LINE INSPECTION, LANDSCAPE AND IRRIGATION PUNCH LIST INSPECTION, AND A LANDSCAPE AND IRRIGATION FINAL INSPECTION.

SEASONS.

4. KEEP PLANTS MOIST AND SHADED UNTIL PLANTING.

9. DEEP WATER ALL PLANTS AT TIME OF PLANTING.

5. DO NOT FERTILIZE FOR AT LEAST ONE GROWING SEASON.

6. AMENDED BACKFILL SHALL BE AS STATED ON THIS SHEET.

- 19. CONTRACTOR IS TO PROVIDE A ONE YEAR WARRANTY ON ALL PLANT MATERIAL, TURF, IRRIGATION COMPONENTS, AND WORKMANSHIP. REPLACEMENT PLANT MATERIALS SHALL BE OF THE SAME SPECIES AND SIZE AS THE DECAYED OR DEAD PLANT MATERIAL. WARRANTY IS VOID IF PLANT MATERIAL ARE UNDER OR OVER-WATERED/FERTILIZED. DAMAGED BY VANDALISM OR NEGLECTED BY OWNER AFTER FINAL MAINTENANCE PERIOD AND FINAL ACCEPTANCE IS PROVIDED.
- REMOVE ALL TREE STAKING MATERIALS AT END OF WARRANTY, PRIOR TO FINAL ACCEPTANCE
- 20. MAINTENANCE: THE OWNER OF THIS PROPERTY AND ANY FUTURE OWNERS SHALL BE RESPONSIBLE FOR THE PROPER LANDSCAPE AND IRRIGATION MAINTENANCE OF THIS SITE AND ANY RIGHT OF WAY AREAS BETWEEN THE CURB AND PROPERTY LINES OF THIS SITE. MAINTENANCE OF THIS SITE INCLUDES, BUT IS NOT LIMITED TO, IRRIGATION INSPECTIONS AND ADJUSTMENTS, IRRIGATION SYSTEM SHUT DOWN AND START UP, IRRIGATION LEAK REPAIR, LANDSCAPE WEEDING, MOWING, SEEDING, FERTILIZATION, WOOD MULCH AND ROCK COVER REPLACEMENT, PRUNING, AND PLANT MATERIAL REPLACEMENT (INCLUDING ANNUAL BEDS). ALL MAINTENANCE SHOULD BE IN ACCORDANCE WITH STANDARDS SPECIFIED WITHIN THE "ALCC SPECIFICATIONS HANDBOOK" REVISED EDITION- 1996. OWNER SHOULD CONTACT LANDSCAPE CONTRACTOR OR LANDSCAPE ARCHITECT REGARDING ANY QUESTIONS RELATING TO THE LANDSCAPE OR IRRIGATION MAINTENANCE OF THIS SITE.

IRRIGATION NOTES

ALL TURF AREAS TO BE IRRIGATED WITH AN AUTOMATIC POP-UP SPRINKLER SYSTEM. ALL SHRUBS BEDS TO BE IRRIGATED WITH AUTOMATIC DRIP IRRIGATION SYSTEM. THE IRRIGATION SYSTEM IS TO BE ADJUSTED TO MEET THE NEEDS OF INDIVIDUAL PLANT MATERIAL.

IRRIGATION SYSTEM TO BE ADJUSTED AS NEEDED FOR PLANT ESTABLISHMENT FOR A PERIOD OF AT LEAST ONE (1) YEAR.

ADJUSTMENTS TO BE MADE AFTER ESTABLISHMENT BASED ON SPECIFIC PLANT REQUIREMENTS. SEE SUGGESTED RUN TIMES PROVIDED WITHIN THESE PLANS.

DESIGN OF IRRIGATION SYSTEMS TO MEET OR EXCEED LOCAL REQUIREMENTS AND INDUSTRY STANDARDS. CONSTRUCTION DOCUMENTS SUITABLE FOR DEVELOPMENT COORDINATION TO BE PROVIDED.

IRRIGATION SYSTEM TO BE DESIGNED USING APPROPRIATE COMPONENTS FOR PLANT MATERIAL, AND WILL INCLUDE A SMART ET CONTROLLER AND RAIN SENSOR.

ALL NATIVE SEED AREAS TO BE TEMPORARILY IRRIGATED.

PLAN NOTES:

- NO SUBSTITUTIONS WITHOUT PREVIOUS APPROVAL OF LANDSCAPE ARCHITECT, 2534 DRC, AND TOWN OF WELLINGTON. UNAPPROVED DEVIATIONS FROM THIS PLAN WILL BE RECTIFIED AT CONTRACTORS EXPENSE. THIS INCLUDES DEVIATIONS OF CULTIVARS FROM THOSE PROPOSED. SEE NOTE #11 FOR ID TAG RETENTION REQUIREMENTS.
- 2. CONTRACTOR TO PROVIDE ANALYSIS OF ANY AMENDMENTS PROPOSED FOR PLANTING AREAS PRIOR TO INSTALLATION OF
- 3. CONTRACTOR TO PROVIDE RECEIPTS TO LANDSCAPE ARCHITECT FOR ALL SEEDING PROPOSED ON SITE, PRIOR TO **INSTALLATION OF SEEDING MATERIALS.**
- 4. NO FABRIC UNDER WOOD MULCH IN ANY AREAS. ALL PLANTS IN ROCK MULCH AREAS TO RECEIVE SHREDDED CEDAR MULCH
- RINGS. MASSING SHALL HAVE CONTINUOUS SHREDDED MULCH BANDS. SEE DETAILS SHEET L2.0. 5. DRIPLINE TO BE PLACED OVER WEED BARRIER FABRIC AND STAKED ON TOP OF WEED BARRIER.
- ALL EMITTERS PER IRRIGATION PLAN.
- 7. ALL EMITTERS TO BE PLACED AT THE APPROPRIATE LOCATIONS. ALL EMITTERS TO USE MICRO TUBING, STAKES, AND BUG
- 8. SEE LANDSCAPE DETAILS SHEET FOR ADDITIONAL NOTES AND DETAILS.
- 9. RETAIN 10% OF ALL PLANT TAGS PER SPECIES FOR DURATION OF WARRANTY PERIOD.

Low Grow Native Seed Mix PBSI Native Low Grow Mix (25%) Idaho Fescue (25%) Sandberg Bluegrass (25%) Rocky Mountain Fescue (25%) Big Bluegrass

Rate: 5 lbs/1000 sf (PLS)

LOW GROW MIX UNLESS OTHERWISE NOTED. RE: CIVIL PLANS

ALL SEED MIXES AS SPECIFIED BY PAWNEE **BUTTES SEED** COMPANY

DISTURBED AREAS TO BE

RESEEDED WITH NATIVE

SEED MAINTENANCE: MOW NATIVE MIX ABOUT ½ THE AMOUNT AS SODDED TURFGRASS OR AS NEEDED. HAND PULL WEED OR SPOT WEED USING A BROADLEAF APPLICATION DURING FIRST 3 GROWING SEASONS.

NATIVE SEED TO BE WATERED VIA TEMPORARY IRRIGATION UNTIL ESTABLISHED, FOR A PERIOD OF APPROXIMATELY 6 WEEKS.

LANDSCAPE REQUIREMENTS INIMUM OVERALL LANDSCAPE AREA REQUIRED = 20% - 53.69% PROVIDED LANDSCAPE AREA Total Landscape Area Total Landscape Area Total Tree Req./Prov. (1/1000 sf landscape) Required (20%) Provided (on-site) 9 trees sub'd for shrubs PARKING LOT LANDSCAPE Parking Screening Length / SF Total Tree Req./Prov. (1/40 LF) Parking Screening Mixed Shrubs / grasses STREETSCAPE LANDSCAPE Street Name or Tree/If No. of Trees Zone Boundary (elev.) Street Classification Minor Collector Footage 440 Req. / Prov. Required 1 / 40 lf Minor Arterial 435 1 / 40 lf BUFFERING LANDSCAPE Linear Zone Boundary (elev.) Footage 760 Provided 10' Required

1. DO NOT REMOVE OR CUT LEADER.


NOT TO SCALE


L2.0

- 2 PRUNE ONLY DEAD OR BROKEN BRANCHES IMMEDIATELY PRIOR TO PLANTING. 3. DO NOT REMOVE ANY DOUBLE LEADER, UNLESS OTHERWISE DIRECTED BY OWNERS REPRESENTATIVE.
- 4. KEEP PLANTS MOIST AND SHADED UNTIL PLANTING. 5. AMENDED BACKFILL SHALL BE AS STATED ON THIS SHEET.
- 6. MARK THE NORTH SIDE OF TREE IN THE NURSERY, AND ROTATE TREE TO FACE NORTH AT THE SITE WHENEVER POSSIBLE
- 7. PINE AND SPRUCE TREES TO BE SPRAYED FOR IPS BARK BEETLE PRIOR TO PLANTING. COORDINATE WITH
- TOWN FORESTRY FOR CURRENT INSECT AND DISEASE RECOMMENDATIONS PRIOR TO PLANTING.

EVERGREEN TREE PLANTING DETAIL

8. ALL TREES TO BE DEEP WATERED AT TIME OF PLANTING.





SECTION

1. MARK THE NORTH SIDE OF TREE IN THE NURSERY, AND ROTATE TREE TO FACE NORTH AT THE SITE

2. AT TIME OF PLANTING, DO NOT REMOVE OR CUT LEADER AND PRUNE ONLY DEAD OR BROKEN BRANCHES, CROSS


OVER BRANCHES, AND WEAK OR NARROW CROTCHES. SOME INTERIOR TWIGS AND LATERAL BRANCHES MAY BE


PRUNED. HOWEVER, DO NOT REMOVE THE TERMINAL BUDS OF BRANCHES THAT EXTEND TO THE EDGE OF THE

3. STRUCTURAL PRUNING SHOULD NOT BEGIN UNTIL AFTER ESTABLISHMENT PERIOD, USUALLY TWO GROWING

7. WRAP TRUNK ON EXPOSED SITES AND SPECIES WITH THIN BARK. USE ELECTRICAL OR DUCT TAPE, NOT TWINE.

8. COORDINATE WITH TOWN FORESTRY FOR CURRENT INSECT AND DISEASE RECOMMENDATIONS PRIOR TO





NO 1ES:

1. KEEP PLANTS MOIST AND SHADED UNTIL PLANTING.


2. PLANT GROUND COVERS AND PERENNIALS LEVEL AND AT GRADE.

3. PRUNE ALL DEAD OR BROKEN PARTS PRIOR TO PLANTING.

4. AMENDED BACKFILL SHALL BE 1/3 COMPOST (PREFERBLY CLASSIFIED) AND 2/3 NATIVE AND/OR IMPORTED TOPSOIL.

5. ALL PERENNIALS PLANTED IN ROCK MULCH AREAS TO HAVE ORGANIC MULCH RINGS AROUND THE BASE OF THE PLANT.

PLACE AS PER PLANS



DATE: 04.01.25 SCALE: DRAWN: JRO CHKD BY: JO

SHEET LANDSCAPE **DETAILS**


NO WE

 \Box

SHREDDED REDWOOD CEDAR / GORILLA

HAIR MULCH ONLY

See Sheet



MCV Master Control Valve

FS Flow Sensor

FP Drip Flush Point

RAIN BIRD PEB

RAIN BIRD PEB

RAIN BIRD XCZ-100-PRF

RAIN BIRD XCZ-100-PRF 1"

RAIN BIRD XCZ-100-PRF 1"

TURF ROTARY

TURF ROTARY

AREA FOR DRIP EMITTERS

AREA FOR DRIP EMITTERS TBD 25 37.1

AREA FOR DRIP EMITTERS TBD 25 37.1

5.53 42.2 54.9

TBD 25 37.1

IRRIGATION NOTES

Note: QUANTITIES ARE LISTED FOR REFERENCE ONLY. CONTRACTOR TO USE GRAPHIC QUANTITIES TO DETERMINE TOTAL EQUIPMENT TYPES AND QUANTITIES. (SEE PLAN GRAPHIC AND EQUIPMENT SCHEDULE). PROVIDE ADDITIONAL IRRIGATION LABOR & COMPONENTS TO PROVIDE HEAD TO HEAD COVERAGE IN THE FIELD FOR ALL SODDED IRRIGATION ZONES AND (90%) OF HEAD TO HEAD COVERAGE FOR SEEDED TURFGRASS AND DRIP TO ALL PLANTINGS.

1. THE IRRIGATION SYSTEM P.O.C. TO BE LOCATED IN THE LANDSCAPE OFF OF THE WATER SUPPLY AS SHOWN PER PLAN, CONNECT TO 3/4" DEDICATED IRRIGATION METER (w/WATTS 223-HP PRV VALVE for Meter Pits Only) AND MININMUM STATIC WATER PRESSURE OF 70 PSI. CONNECTION IS ASSUMED TO PROVIDE MINIMUM 10.2 GPM. COORDINATE WITH OWNER'S REPRESENTATIVE AND OTHER TRADES TO ESTABLISH WATER CONNECTION AT LOCATION SHOWN AND ALL SLEEVING INSTALLED. NOTIFY DESIGN OF ANY DEVIATIONS IN PRESSURE OR GPM. FAILURE TO NOTIFY LANDSCAPE ARCHITECT WILL RESULT IN CONTRACTOR ASSUMING LIABILITY FOR ANY UNAUTHORIZED CHANGES MADE.

2. THE SYSTEM CONTROLLER IS TO BE A WALL MOUNT IN GENERAL LOCATION SHOWN. COORDINATE LOCATION OF CONTROLLER AND RAIN SENSOR WITH OWNER. CONNECT CONTROLLER TO POWER SUPPLY (COORDINATE WITH OWNER), ZONE VALVE WIRES, RAIN SENSOR, AND GROUNDING. INSTALL AS PER MANUFACTURER'S INSTRUCTIONS. PROVIDE LIGHTNING PROTECTION FOR ALL CONTROLLERS (TYPICAL).

3. COORDINATE ALL UNDERGROUND UTILITY LOCATIONS PRIOR TO ANY DIGGING ON SITE. ALL MATERIALS AND INSTALLATION PRACTICES ARE TO BE IN COMPLIANCE WITH LOCAL CODES.

4. CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ALL IRRIGATION SLEEVING REQUIRED TO PERFORM WORK AS SHOWN PER PLAN. SLEEVING FOR LATERAL LINES IS TO BE 24" UNDERGROUND. MAINLINE SLEEVING TO BE 36" UNDERGROUND. ALL SLEEVING IS TO EXTEND 18" BEYOND EDGE OF CONCRETE OR ASPHALT. ENDS OF SLEEVING ARE TO BE SECURELY COVERED AFTER INSTALLATION. SLEEVE LOCATIONS ARE TO BE CLEARLY MARKED/STAMPED. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL SLEEVING LOCATIONS PRIOR TO CONSTRUCTION AND INSTALL ANY MISSING SLEEVES, IF NECESSARY.

5. ALL SPRINKLER HEADS SHALL BE INSTALLED WITH THE TOP OF HEADS FLUSH WITH SURROUNDING FINAL GRADE. CONTRACTOR IS TO ADJUST EACH SPRINKLER HEAD TO PROVIDE OPTIMAL COVERAGE. OVERSPRAY ONTO PAVEMENT OR WALLS IS TO BE MINIMIZED. CONTRACTOR IS TO ADJUST AND SELECT NOZZLES TO PROVIDE UNIFORM COVERAGE. PROVIDE PRESSURE COMPENSATING NOZZLES OR SCREENS IF UNIFORM PRESSURE CANNOT BE ACHIEVED BY ADJUSTING PRESSURE AT VALVES. CONTRACTOR TO REPAIR ALL IRRIGATION EROSION/GULLIES IN SEEDED AREAS FORMED BY SPRAY AND GEAR HEADS FOR THE FIRST 45 DAYS AFTER FINAL APPROVAL IS PROVIDED BY THE OWNER OR LANDSCAPE ARCHITECT.

6. IRRIGATION PLAN IS DIAGRAMMATIC. ANY COMPONENTS SHOWN ON PLAN OUTSIDE OF LANDSCAPE ARE SHOWN FOR CLARITY ONLY. USE ONLY STANDARD FITTINGS. MAINLINE PIPING DEPTH IS TO BE 24". LATERAL LINE DEPTH IS TO BE 12". POLY DRIP LINE IS TO BE SECURED AT FINAL SOIL GRADE. POLY LINE SHALL BE COMPLETELY COVERED WITH MULCH WITH NO LINE EXPOSED. GRAPHIC QTY'S. PREVAIL OVER WRITTEN QTY'S. INSTALL MAINLINE AND LATERALS AS CLOSE TO CURBS AND SIDEWALKS AS POSSIBLE TO ALLOW FOR MORE PLANTING ROOM.

7. CONTRACTOR IS TO INSTALL #14 UF IRRIGATION WIRE BETWEEN CONTROLLER AND ELECTRIC VALVES.

8. INSTALL THREE EXTRA WIRES FROM THE CONTROLLER ALONG THE MAINLINE IN EACH DIRECTION FROM THE CONTROLLER FOR TROUBLE SHOOTING AND FUTURE ADDITIONS. ADDITIONAL WIRES TO BE PLACED IN A 6" VALVE BOX FOR EASY FUTURE 9. NOTIFY LANDSCAPE ARCHTIECT OF ANY DISCREPANCIES BETWEEN PLAN DRAWINGS

AND CONDITIONS IN THE FIELD PRIOR TO INSTALLATION OF ANY IRRIGATION COMPONENTS. 10.CONTRACTOR TO KEEP ALL PRESSURIZED IRRIGATION SUPPLY PIPE, (INCLUDING

MAIN LINE, LATERALS, AND DRIP SUPPLY TUBING) AS WELL AS POP-UP SPRAY OR GEAR DRIVE HEADS A MIN. OF 5' AWAY FROM THE BUILDING OR AS NOTED BY THE SOILS ENGINEERS REPORT. THE MOST STRINGENT REQUIREMENT SHALL PREVAIL. ENSURE THAT POSITIVE DRAINAGE IS PROVIDED AND THAT NO IRRIGATION COMPONENTS NEGATIVELY IMPACT HARD SURFACES AND/OR BUILDING FOUNDATIONS.

11. CONTRACTOR TO PROVIDE A ONE YEAR WARRANTY ON ALL IRRIGATION PARTS AND WORKMANSHIP. CONTRACTOR IS TO PROVIDE AS-BUILT DRAWINGS TO OWNER ALONG WITH QUICK-COUPLER KEYS WITHIN 30 DAY OF FINAL ACCEPTANCE FROM OWNER OR LANDSCAPE ARCHITECT.

12. THE OWNER OF THIS PROPERTY AND ANY FUTURE OWNERS SHALL BE RESPONSIBLE FOR THE PROPER IRRIGATION MAINTENANCE OF THIS SITE. MAINTENANCE OF THIS SITE INCLUDES, BUT IS NOT LIMITED TO, IRRIGATION INSPECTIONS AND ADJUSTMENTS, IRRIGATION SYSTEM SHUT DOWN AND START UP. IRRIGATION LEAK REPAIR, IRRIGATION HEAD REPLACEMENT, RAIN SENSOR ADJUSTMENT, IRRIGATION CONTROLLER ADJUSTMENTS, DRIP IRRIGATION MAINTENANCE AND VERIFICATION THAT ALL LANDSCAPE AREAS ARE NOT OVER-WATERED OR UNDER-WATERED. ALL MAINTENANCE SHOULD BE IN ACCORDANCE WITH STANDARDS SPECIFIED WITHIN THE "ALCC SPECIFICATIONS HANDBOOK" REVISED EDITION- 1996. OWNER SHOULD CONTACT THE LANDSCAPE MAINTENANCE CONTRACTOR, LANDSCAPE CONSTRUCTION CONTRACTOR, OR LANDSCAPE ARCHITECT REGARDING ANY QUESTIONS RELATING TO THE LANDSCAPE OR IRRIGATION MAINTENANCE OF THIS SITE.

13. SHOULD LOCAL UTILITIES, WATER OR SPECIAL DISTRICTS DESIGNATE SPECIFIC WATER CONTROLS, IRRIGATION SCHEDULES SHALL BE ADJUSTED PURSUANT TO JURISDICTION REQUIREMENTS.

14. ADJUST IRRIGATION ZONE RUN TIMES WITH SEASONAL CONDITIONS. REDUCE RUN TIMES ACCORDING TO SEASONAL ADJUSTMENT SCHEDULE AND BASED ON SMART CONTROLLER ADJUSTMENTS (EXCEPT FOR NEW INSTALLATIONS DURING THE FIRST GROWING SEASON).

15. PROVIDE DRIP IRRIGATION TO ALL EXISTING TREES AND SHRUBS IMPACTED BY CONSTRUCTION. PROVIDE ONE-HALF THE AMOUNT OF EMITTER DEVICES THAT ARE DESIGNATED FOR NEW PLANT MATERIAL 16. DRIP ZONES REQUIRE PRESSURE REGULATORS AND FILTERS WITH A MIN. 150 MESH

SCREEN OR APPROVED EQUAL. 17. PRESSURE COMPENSATING EMITTER OR APPROVED EQUAL MAY BE USED WITH MICRO-TUBING AND INSECT CAPS TO DIRECT WATER TO AREAS THAT REQUIRE SPOT

18. LINE FLUSHING VALVES ARE TO BE LOCATED AT THE END OF EACH DRIP ZONE. INSTALL IN A 6" VALVE BOX W/ FILTER FABRIC & 4" OF CLEAN GRAVE BELOW EACH

19. USE MICRO-SPRAY EMISSION DEVICES OR DRIPLINE FOR IRRIGATION OF ALL ANNUAL, AND GROUND COVER BEDS. LOCATED ON FLEXIBLE RISERS/STAKES. ADJUST SPRAY OUTPUT FOR PLANT COMMUNITY WATER INTAKE REQUIREMENTS. 20. NEW SOD WATER REQUIREMENTS: 1" OF WATER/DAY FOR 7 DAYS. TOTAL AMOUNT SPLIT UP OVER 4 TO 5 WATERING PERIODS. DURING WARMER PERIODS APPLY 1.25-1.50"/DAY. AFTER WEEK 2 APPLY 1/4" TO 1/2" PER DAY FOR 9 DAYS. SPLIT UP OVER 1 TO 3 WATERING PERIODS/DAY. IF WATERING RESTRICTIONS ALLOW WATER 1/4"/DAY EVERY OTHER DAY FOR 7 DAYS. AFTER TURF ESTABLISHMENT TIME REFER TO SCHEDULE AND LOCAL RESTRICTIONS FOR RUN TIMES.

21. MOVE SPRINKLER HEADS OR TREE LOCATIONS IF SPRAY OR GEAR DRIVE HEADS ARE IN CONFLICT WITH ONE ANOTHER (I.e., within 5' of sprinkler head). 22. US HARCO SCH 40 RATED FITTINGS FOR ALL SYSTEMS. USE EPOXY DUCTILE IRON FITTINGS AND ADJUSTABLE PIPE CLAMPS FOR SYSTEMS USING OVER 80 PSI AT

REFERENCE NOTES SCHEDULE

SYMBOL DESCRIPTION DIAGRAMMATIC DRIPLINE. ROUTE AS NECESSARY IN FIELD. QUANTITIES WILL VARY FROM THOSE SHOWN ON PLAN. ADJUST HEADS AS NECESSARY TO AVOID OVERSPRAY WHILE MAINTAINING PROPER COVERAGE. RADII MUST BE ADJUSTED PRIOR TO INSPECTION. RADII MAY BE ADJUSTED UP TO 25%. PROVIDE ADDITIONAL HEADS IF REQUIRED. ADJUST LOCATIONS TO AVOID TREE CONFLICTS, ETC. PROVIDE TWO (2) SLEEVES AT ALL MAINLINE CROSSINGS--ONE FOR PIPE AND ONE FOR WIRING.

ALL LOCATIONS DIAGRAMMATIC FOR CLARITY. LOCATE IN LANDSCAPE BEDS. FIELD ADJUST AS NECESSARY AND PROVIDE RECORD VIA AS-BUILTS. SEE NOTES.

ALL DRIP SUPPLY TUBING TO BE 3/4\". ALL MICRO TUBING TO BE 1/4\" AND STAKED AT EDGE OF ROOTBALL. PROVIDE EMITTERS PER SCHEDULE. PROVIDE BUG CAP AT TERMINUS OF ALL MICRO TUBING RUNS, ALL DRIP LINE TO BE PLACED OVER WEED BARRIER FABRIC (WHERE APPLICABLE).

EXTEND TWO SPARE CONTROL WIRES WITH COMMON FROM

PLACE ALL PRESSURIZED LINES MIN 5' AWAY FROM BUILDING WHEREVER POSSIBLE, TYP.

CONTROLLER TO GENERAL LOCATION SHOWN. PLACE IN QUICK COUPLING VALVE BOX WITH QC VALVE FOR FUTURE EXPANSION. NATIVE TURF AREAS TO BE TEMPORARILY IRRIGATED UNTIL

ESTABLISHED

DATE: 04.01.25 SCALE: See Sheet DRAWN: JRO CHKD BY: JO

SHEET **IRRIGATION**

Page 43 of 59

_	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	PS
>		HUNTER MP2000 PROS-06-PRS40-CV TURF ROTATOR, 6IN. POP-UP WITH FACTORY INSTALLED CHECK VALVE, PRESSURE REGULATED TO 40 PSI, MP ROTATOR NOZZLE ON PRS40 BODY. K=BLACK ADJ ARC 90-210, G=GREEN ADJ ARC 210-270, R=RED 360 ARC.	33	40
}	SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	
}	•	RAIN BIRD XCZ-100-PRF MEDIUM FLOW DRIP CONTROL KIT, 1" DV VALVE, 1" PRESSURE REGULATING FILTER, 40PSI PRESSURE REGULATOR. 3GPM - 15GPM. USE LOW FLOW MODEL FO FLOWS UNDER 3 GPM	3 DR	
{	Φ	FLUSH VALVE 3/4" PVC BALL VALVE IN 10" VALVE BOX.	15	
		AREA TO RECEIVE DRIP EMITTERS RAIN BIRD XB-PC SINGLE OUTLET, PRESSURE COMPENSATING DRIP EMITTERS. FLOW RATES OF 0.5GPH=BLUE, 1.0GPH=BLA AND 2.0GPH=RED. COMES WITH A SELF-PIERCING BARE INLET X BARB OUTLET.	•	
	+ + + + + + + + + + + + + + + + + + +	PERENNIALS TO RECEIVE ONE OF 0.5 GPH EMITTERS GRASSES TO RECEIVE ONE OF 1.0 GPH EMITTERS SHRUBS TO RECEIVE TWO OF 1.0 GPH EMITTERS TREES TO RECEIVE TO RECEIVE MINIMUM FOUR OF 2.0 GPH EMITTERS		
>	<u>SYMBOL</u>	MANUFACTURER/MODEL/DESCRIPTION	QTY	
}	•	RAIN BIRD PEB 1", 1-1/2", 2" PLASTIC INDUSTRIAL VALVES. LOW FLOW OPERATING CAPABILITY, GLOBE CONFIGURATION.	4	
		RAIN BIRD 5-LRC 1" BRASS QUICK-COUPLING VALVE, WITH CORROSION-RESISTANT STAINLESS STEEL SPRING, LOCKING THERMOPLASTIC RUBBER COVER, AND 1-PIEC BODY.	4 E	
	X	NIBCO T-113-K CLASS 125 BRONZE GATE SHUT OFF VALVE WITH CROSS HANDLE, SAME SIZE AS MAINLINE PIPE DIAMETER AT VALVE LOCATION. SIZE RANGE - 1/4" - 3"	5 1	
		RAIN BIRD PESBR 1" 1IN., 1-1/2IN., 2IN. DURABLE CHLORINE-RESISTANT MAST VALVES FOR RECLAIMED WATER APPLICATIONS. WITH SCRUBBER MECHANISM TECHNOLOGY, AND PURPLE FLOW CONTROL HANDLE.	ER ₁	
	→ → → →	MANUAL DRAIN VALVE PROVIDE 10" ROUND BOX WITH 2" VALVE MARKER, PVC ACCESS SLEEVE, AND MINIMUM 6" DEPTH 3/4" WASHED RIVER ROCK SUMP FOR DRAINAGE. PROVIDE 3/4" MXF SCH 40 PVC 90 ELL AND 3/4" X 4" SCH 80 PVC NIPPLE TO SUMP FOR DRAINAGE. USE TEFLON TAPE ON ALL MALE THREADED PVC AND AND ALL NIPPLES	1	
5 ((BF	FEBCO 825YA 3/4" REDUCED PRESSURE BACKFLOW PREVENTER	1	
(> >	RAIN BIRD ESP4ME3 WITH (1) ESP-SM3 7 STATION, HYBRID MODULAR OUTDOOR CONTROLLER. FOR RESIDENTIAL OR LIGHT COMMERCIAL USE. LNK WIF MODULE AND FLOW SENSOR READY.		
(RS	RAIN BIRD WR2-RFS WIRELESS RAIN/FREEZE SENSOR.	1	
— ((\$ } }	GUARDSHACK EC-2 GUARDSHACK ECONOCAGE, WITH EP-1 AND FG-1. INST PER MANUFACTURER REQUIREMENTS AND VERIFY LOCKING HARDWARE PRIOR TO TURNOVER.	ALL 1	
(M	WATER METER 3/4" CONNECT TO STUB OUT IN GENERAL LOCATION SHOWN COORDINATE WITH CIVIL/MECHANICAL	. 1	
(>	IRRIGATION LATERAL LINE: PVC CLASS 160 SDR 26	551.5 LF	
(} — — —	IRRIGATION MAINLINE: PVC CLASS 200 SDR 21	831.7 LF	
((} } }	PIPE SLEEVE: PVC SCHEDULE 40 PIPE SLEEVE SIZE SHALL ALLOW FOR IRRIGATION PIPIN AND THEIR RELATED COUPLINGS TO EASILY SLIDE THROUGH SLEEVING MATERIAL. SLEEVES TO BE MINIM 2X PIPE DIAMETER UNLESS OTHERWISE NOTED.EXTENDE SLEEVES 18 INCHES BEYOND EDGES OF PAVING OR CONSTRUCTION.	UM 346.2 LF)	
	\	1.5"		

CONSIST OF T


- CHECK HE REPLACE RE-PROGF OFTEN IF NEEDS
- VERIFY TH ARE AS S INSPECT DETERMIN PERIODIC IRRIGATIO CHECK VALVES TO MAKE SURE THEY ARE
- ENSURE DRIP EMITTERS ARE NOT BROKEN OR
- ADJUST COMPONENTS AS NECESSARY OR AS PLANT

A SEASONAL MAINTENANCE SCHEDULE SHALL BF PERFORMED (

ON THE IRRIGATION SYSTEMS AND SHALL THE FOLLOWING ITEMS:	<u>Month</u>	Seaso Adjustr Fact
EADS FOR COVERAGE AND LEAKAGE EALL BROKEN HEADS	April	
RAM CONTROLLERS MONTHLY OR MORE NECESSARY ACCORDING TO THE SEASONAL	May	
HAT THE WATER SUPPLY AND PRESSURE	June	
STATED IN THE DESIGN	July	1
THE BACKFLOW PREVENTION DEVICE TO NE IF IT IS WORKING CORRECTLY	August	
CALLY VERIFY THAT SENSORS IN THE ON SYSTEM ARE WORKING PROPERLY	September	
ALVECTO MAKE CLIDE THEY ARE		

FUNCTIONING PROPERLY CHECK HEADS AND EMITTERS FOR DEBRIS

GROWTH DICTATES



BUILDING WELI

DATE: 04.01.25
SCALE: See Sheet
DRAWN: JRO
CHKD BY: JO

SHEET
IRRIGATION
DETAILS

14 of 16

SITE DEVELOPMENT PLAN

KRI WELLINGTON - LOT 1A BONFIRE SUB 3RD FILING

LOT 1A, BLOCK 1, BONFIRE SUBDIVISION 3RD FILING

BEING A REPLAT OF LOTS 1 & 2, BLOCK 2 OF BONFIRE SUBDIVISION, 2ND FILING


LOCATED IN PART OF THE SOUTHEAST QUARTER OF SECTION 27 TOWNSHIP 9 NORTH, RANGE 68 WEST OF THE 6TH PRINCIPAL MERIDIAN TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADo

+0.0 +0.0 FUTURE PARKING +0.0 +0.0 +0.0 +0.0 0.0 +0.0 +0.0 0.0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 0.0 +0.0 +0.0 .0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 .0 +0.0 +0.0 0.0 +0.0 +0.0 +0.0 +0.0 0.0 +0.0 +^{0.0} +^{0.0} +^{0.0} 0.0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 .0 +0.0 +0.0 0.0 +0.0 +0.0

PHOTOMETRIC PLAN NOTES:

- ALL LIGHTING SHALL BE IN COMPLIANCE WITH THE CITY OF WELLINGTON MUNICIPAL CODE AND OUTDOOR LIGHTING ORDINANCES.
- LIGHTING LEVELS SHALL NOT EXCEED 0.1 FOOTCANDLES AT 20 FEET PAST PROPERTY LINE.
- 3. ALL FIXTURES SHALL BE FULL CUTOFF.
- 4. ALL FIXTURE HEIGHTS SHOWN ON PLAN ARE FROM GRADE TO BOTTOM OF FIXTURE.

Statistics										
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min				
PROPERTY LINE	+	0.1 fc	0.4 fc	0.0 fc	N/A	N/A				
SITE	+	1.3 fc	10.2 fc	0.0 fc	N/A	N/A				
WEST PARKING	\times	2.3 fc	4.2 fc	1.1 fc	3.8:1	2.1:1				
20' PAST PROPERTY LINE	+	0.0 fc	0.1 fc	0.0 fc	N/A	N/A				



REVISIONS

NOT FOR CONSTRUCTION

PHOTOMETRIC PLAN

SITE DEVELOPMENT PLAN

KRI WELLINGTON - LOT 1A BONFIRE SUB 3RD FILING

LOT 1A, BLOCK 1, BONFIRE SUBDIVISION 3RD FILING

BEING A REPLAT OF LOTS 1 & 2, BLOCK 2 OF BONFIRE SUBDIVISION, 2ND FILING

LOCATED IN PART OF THE SOUTHEAST QUARTER OF SECTION 27 TOWNSHIP 9 NORTH, RANGE 68 WEST OF THE 6TH PRINCIPAL MERIDIAN TOWN OF WELLINGTON, COUNTY OF LARIMER, STATE OF COLORADo

LIGHTING FIXTURE SCHEDULE


(P.E.C. - FT. COLLINS)

1. MANUFACTURERS LISTED IN THIS SCHEDULE OR APPROVED BY WRITTEN ADDENDUM WILL BE THE ONLY APPROVED MANUFACTURERS TO BID THE LIGHTING FIXTURES FOR THIS PROJECT. CONTRACTORS AND SUPPLIERS USING PRICING FROM MANUFACTURERS NOT LISTED ON SCHEDULE OR BY ADDENDUM DO SO AT THEIR OWN RSK.

2. LIGHT FIXTURE SELECTIONS ARE BASED ON THE MANUFACTURER IN THE LEFT MOST COLUMN AS LISTED IN THE SCHEDULE. FIXTURES APPROVED AS EQUALS IN THIS SCHEDULE OR BY ADDENDUM SHALL BE EQUAL TO THE UNIT SPECIFIED IN THE LEFT MOST COLUMN, IE: SPRING LOADED LATCHES, POST PAINTED FINISH. PHOTOMETRICS.

MARK	DESCRIPTION	MANUFACTURER 1 CATALOG NUMBER	LIGHT SOURCE			E	LENS/LOUVER/FINISH	DIMENSIONS REF.			REF.	REMARKS
			#	TYPE	WATTS	VOLTS	LENS/LOUVER/FINISH	W	L	D	NOTE	REWARRS
P32	EXTERIOR AREA LIGHT - TYPE IV	MCGRAW-EDISON GLEON-SA2C-730-U-T4FT	1	LED	113	UNV		1.29	1.81	0.33		14500LM 3000K 70CRI
WA1E	EXTERIOR WALL PACK - MANDOOR EM	MCGRAW EDISON IST-SA1-B-730-U-T4FT-XX	1	LED	29	UNV	DARK BRONZE	1.15	1.25	0.77		3500LM; 3000K; 70CRI
WA2	EXTERIOR WALL PACK - AREA TYPE FT	MCGRAW EDISON GAW-SA1C-730-U-T4W	1	LED	59	UNV	DARK BRONZE	1.15	1.25	0.77		7600LM; 3000K; 70CRI
WA3	EXTERIOR WALL PACK	MCGRAW EDISON IST-SA1-B-730-U-SL3-XX	1	LED	29	UNV	DARK BRONZE	1.15	1.25	0.77		3500LM; 3000K; 70CRI
WA4	EXTERIOR WALL PACK - AREA TYPE IV	MCGRAW EDISON GAW-SA2D-730-U-SL4	1	LED	129	UNV	DARK BRONZE	1.15	1.25	0.77		15400LM; 3000K; 70CRI


TYPES P32





- **常** Interactive Menu
- Ordering Information page 2 Mounting Details page 3
- Optical Distributions page 4 • Product Specifications page 4
- Energy and Performance Data page 4 • Control Options page 9
- **Quick Facts**
- Lumen packages range from 4,200 80,800 (34W - 640W)
- Efficacy up to 156 lumens per watt
- Options to meet Buy American and other domestic preference requirements

Dimensional Details



"A" Width	Standard Arm Length	Extended Arm Length ¹	Quick Mount Arm Length	Quick Mou Extended Arm Lengt	
15-1/2"	7"	10"	10-5/8"	16-9/16	
21-5/8"	7"	10"	10-5/8"	16-9/16	
27-5/8"	7"	13"	10-5/8"		
33-3/4"	7"	16"			
quirements and additi	onal line art, see Moun	iting Details section.			
	21-5/8" 27-5/8" 33-3/4"	"A" Standard Arm Length 15-1/2" 7" 21-5/8" 7" 27-5/8" 7" 33-3/4" 7"	"A" Width Standard Arm Length 1 15-1/2" 7" 10" 21-5/8" 7" 10" 27-5/8" 7" 13"	"A" Width Standard Arm Length Extended Arm Length 1 Quick Mount Arm Length 15-1/2" 7" 10" 10-5/8" 21-5/8" 7" 10" 10-5/8" 27-5/8" 7" 13" 10-5/8" 33-3/4" 7" 16"	

Product Certifications


★ Connected Systems

WaveLinx

Enlighted

COOPER PS500020EN page 1 June 14, 2022 5:49 PM

TYPE WA1E, WA3



McGraw-Edison

Impact Elite LED

Wall Mount Luminaire

Product Certifications


Connected Systems

WaveLinx

Enlighted








• Control Options page 4


Quick Facts 10 Optical Distributions Lumen packages range from 2,459 to 8,123 (20W - 66W) Efficacy up to 143 lumens per watt



COOPER

PS500049EN page 1 November 30, 2021 10:39 AM

TYPES WA2, WA4





Interactive Menu Ordering Information page 2

• Control Options page 6


• Product Specifications page 2 Optical Distributions page 3 Energy and Performance Data page 4


IP66 PERIFIED SAFETY STATEFORE STATEFORE STATEFORE SAFETY

Quick Facts Choice of thirteen high-efficiency, patented AccuLED

 Downward and inverted wall mounting configurations • Eight lumen packages from 3,215 up to 17,056 Efficacies up to 154 lumens per watt

Dimensional Details





NOTES:

1. Visit https://www.designlights.org/search/ to confirm qualification. Not all product variations are DLC qualified.

2. IDA Certified for 3000K CCT and warmer only.

COOPER

351 LINDEN ST., SUITE 100 FT. COLLINS, CO 80524 970-232-9558 www.pec1.com

REVISIONS

NOT FOR CONSTRUCTION

KRI WELLINGTON

Connected Systems Enlighted

Streetworks

GAW Galleon Wall

Wall Mount Luminaire

Product Certifications

Product Features

PHOTOMETRIC DETAILS

CHECKED BY

Planning Commission Regular Meeting

Amended Site Development Plan for Kaufman & Robinson Inc.

Presented By: Aidan Checkett, Planner I Town of Wellington Planning Department

Monday, June 2, 2025



SITE LOCATION MAP





Property Background

- A site development plan was previously approved by the Planning Commission on November 7, 2022. The plan approval is valid through November 7, 2025.
- The owner has submitted a development plan application to amend the previously approved site development plan.
- The applicant has also applied for a lot-line adjustment to combine the two lots as required.



Property Background (continued)

- Changes to approved site development plans that exceed 10% of any measurable standard require Planning Commission review and approval [Sec. 15-2-120(c)].
 - Building height is proposed to increase from 28 ft. to 37 ft. (exceeds 10%)
 - Minor changes to the building footprint, landscaping, parking, and illumination
- A review of an amendment to the site plan should consider the elements of the site development plan that are different from the approved plan.




Findings For Approval – Site Development Plan

- 1. The site development plan is consistent with the Comprehensive Plan and the intent stated in this Land Use Code.
- 2. The lot size and lot dimensions are consistent with what is shown on the approved final plat.
- 3. No buildings or structures infringe on any easements.
- 4. The proposed site grading is consistent with the requirements of any applicable adopted storm drainage criteria or master drainage plans.
- 5. The density and dimensions shown conform with Article 4 of this Code or the approved PUD requirements.
- 6. The applicable development standards have been adequately addressed and the proposed improvements conform with Article 5 of this Code.



Site Plan





- 1. Compliance with Land Use Code and Comprehensive Plan
- Zoning: Light Industrial
- Comprehensive Plan: Industrial
- Proposed uses: professional office, light industrial and manufacturing, and wholesale distribution, warehousing, and storage
- Finding previously made, no changes
- 2. Consistency with Approved Final Plat
- Lot size and lot dimensions have not changed since the approved site development plan
- Property will need a lot line adjustment



- 3. Easement Access
- No buildings or structures infringe on any easements
- Easements have not been changed from the approved site development plan

- 4. Drainage Standards
- There are no changes proposed to drainage plans
- Town Engineer determined that drainage meets Town standards



- 5. Density and Dimensions
- Residential density and PUD requirements are not applicable
- Floor Area Ratio is less than 1:1, and meets the LI zone standard
- Setbacks are satisfied
- Building height proposed increase from 28 ft. to 37 ft. and meets the 45 ft. maximum building height of the LI zone



- 6. Conformity with Development Standards
- Parking and Loading
 - Minor changes to locations
- Landscaping and Screening
 - Minor changes to south and west of site
 - Recommend relaxing requirements for east side
- Exterior Lighting
 - Minor changes proposed (additional light fixtures by northwest building corner, fixtures relocated on east side of building)
 - o Town standards for foot-candle minimums and maximums are satisfied



- 6. Conformity with Development Standards (cont.)
- Site and Building Design
 - oHeight increased (28 ft. to 37 ft.)
 - Minor changes to building footprint
- Utilities
 - No changes made
 - o Engineering and Public Works recommended minor updates to labels
- Transportation and Connectivity
 - No changes to driveways and circulation



Staff Recommendation

Move to approve the amended site development plan subject to addressing Planning and Engineering comments.



Questions or Comments?

